

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

API NO. 15- 033-20875 - 6000

Operator: License # 3882

Name: SAMUEL GARY JR. AND ASSOC.

Address: 1775 SHERMAN ST., SUITE 1925

City/State/Zip: DENVER, CO 80203

Purchaser: N/A

Operator Contact Person: CRAIG AMBLER

Phone (303) 831-4673

Contractor: Name: H-40 DRILLING, INC.

License: 30692

Wellsite Geologist: TIM MCCOY

Designate Type of Completion

New Well Re-Entry Workover

Oil SWD SLOW Temp. Abd.

Gas ENHR SIGW

Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover:

Operator:

Well Name:

Comp. Date Old Total Depth

Deepening Re-perf. Conv. to Inj/SWD

Plug Back PBTD

Commingled Docket No.

Dual Completion Docket No.

Other (SWD or Inj?) Docket No.

JUNE 24, 1993 JULY 3, 1993 JULY 4, 1993
Spud Date Date Reached TD Completion Date

County COMANCHE

NE - SE - SW - Sec. 8 Twp. 34S Rge. 20 X W

900 Feet from S/N Line of Section

2350 Feet from E/W Line of Section

Footages Calculated from Nearest Outside Section Corner:
NE, SE, NW or SW

Lease Name SELZER Well # 8-14

Field Name WILDCAT

Producing Formation N/A

Elevation: Ground 1760' KB 1773'

Total Depth 5470' PBTD N/A

Amount of Surface Pipe Set and Cemented at 723 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set Feet

If Alternate II completion, cement circulated from

feet depth to w/ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)

Chloride content 9000 ppm Fluid volume 1360 bbls

Dewatering method used HAULED OFFSITE

Location of fluid disposal if hauled offsite:

Operator Name KBW OIL & GAS

Lease Name HARMON SWD License No. CD 98329

NW Quarter Sec. 11 Twp. 33 S Rng. 20 E/W

County COMANCHE Docket No. 5993

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Samuel Gary, Jr.

Title President Date 08/30/93

Subscribed and sworn to before me this 30th day of August, 1993.

Notary Public Joan S. Lucero

Date Commission Expires 01/21/1996

K.C.C. OFFICE USE ONLY	
F	<input type="checkbox"/> Letter of Confidentiality Attached
C	<input checked="" type="checkbox"/> Wireline Log Received
C	<input checked="" type="checkbox"/> Geologist Report Received
Distribution	
<input checked="" type="checkbox"/> KCC	<input type="checkbox"/> SWD/Rep
<input type="checkbox"/> KGS	<input type="checkbox"/> Plug
NGPA	
RECEIVED	
STATE CORPORATION COMMISSION	

SEP 03 1993
9-3-93
CONSERVATION DIVISION
Wichita, Kansas

Operator Name SAMUEL GARY JR. & ASSOC. Lease Name SELZER Well # 8-14

Sec. 8 Twp. 34S Rge. 20 East
 West County COMANCHE
API # 15-033-20875-0000

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
(Attach Additional Sheets.)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
(Submit Copy.)

List All E.Logs Run: DIL, SONIC, GR
COMP. NEUTRON - PHOTO DENSITY

<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datums	Sample
Name	Top	Datum
STONE CORRAL	813	+960
WABAUNSEE	3270	-1497
HEEBNER	4226	-2453
LANSING	4418	-2645
STARK	4854	-3081
MARMATON	4996	-3223
CHEROKEE	5159	-3386
MORROW	5270	-3497
TOP MISSISSIPPIAN	5383	-3610

CASING RECORD							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12 1/4	8 5/8	24	723	65/35 POZ LITE	225	3% CaCl, 6% GEL 1/4#/SK FLOCEAL
					CLASS "A"	100	3% CaCl, 2% GEL

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumed Production, SWD or Inj.	Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio

Disposition of Gas: Vented Sold Used on Lease (If vented, submit ACO-18.)

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval: _____

RECEIVED
STATE CORPORATION COMMISSION
SEP 03 1993
7-3-93
CONSERVATION DIVISION
Wichita, Kansas

15-033-20875-0000

ORIGINAL

CONDITIONS
Allied Cementing Co., Inc., and "Customer" shall be responsible for the services described on the front of this contract and to any other materials...

TELEPHONE:
AREA CODE 913 483-2627

ALLIED CEMENTING COMPANY, INC.
P. O. BOX 31
RUSSELL, KANSAS 67665

TO: Sam Gary Jr. & Associates
1775 Sherman, Suite 1925
Denver, CO 80203

INVOICE NO. 64265
PURCHASE ORDER NO. _____
LEASE NAME Selzer #8-14
DATE June 25, 1993

SERVICE AND MATERIALS AS FOLLOWS:

Common 271 sks @\$5.75	\$1,558.25	
Pozmix 79 sks @\$3.00 07020758	237.00	
Gel 17 sks @\$7.00	119.00	
Chloride 11 sks @\$25.00	275.00	
Flo Seal 56# @\$1.10	61.60	\$2,250.85
Handling 350 sks @\$1.00	350.00	
Mileage (50) @\$.04¢ per sk per mi	700.00	
Surface	430.00	
Mi @\$2.25 pmp trk chg	112.50	
430' @\$.39¢ over 300'	167.70	
1 plug	83.00	1,843.20
1 Guide Shoe-----	\$240.00	If account <u>CURRENT</u> 20% discount will be allowed <u>ONLY</u> if paid within <u>30</u> days from date of invoice.
1 AFU Insert-----	258.00	
2 Centralizers-----	122.00	
1 Cement Basket-----	180.00	
1 Thread Lock-----	30.00	
		830.00

Thank you! Total

\$4,924.05

All Prices Are Net, Payable 30 Days Following Date of Invoice. 1½% Charged Thereafter.

RECEIVED
STATE CORPORATION COMMISS

SEP 03 1993
9-3-93
CONSERVATION DIVISION
Wichita, Kansas

15-033-20875-0000

ORIGINAL

483-2627, Russell, Kansas
 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812
 Phone Ness City 913-798-3843

ALLIED CEMENTING CO., INC.

1255

Home Office P. O. Box 31

Russell, Kansas 67665

NEW

Date	6/25/93	Sec	9	Twp.	34	Range	20	Called Out	9:00 pm	On Location	11:30	Job Start	3:19	Finish	5:00
Lease	Scizer	Well No.	8-14			Location			Protection 2w 7s E1S			County	Comanche	State	KS

Contractor	H-40 Drilling	
Type Job	8 7/8 Surface Csg.	
Hole Size	12 1/4	T.D. 740.
Csg.	8 7/8 24 #	Depth 730
Tbg. Size		Depth
Drill Pipe		Depth
Tool		Depth
Cement Left in Csg.	43.55	Shoe Joint 43.55
Press Max.	900	Minimum 50
Meas Line		Displace 43.7
Perf.		

Owner SAME
 To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To Sam Gary Jr. & Associates
 Street 1775 Sherman Suite 1925
 City Denver State Colo. 80203

The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No.
x Harry J. Benedick

EQUIPMENT

Pumptrk	No.	Cementor	<u>Max Hall</u>
	<u>234</u>	Helper	<u>Justin Hart</u>
Pumptrk	No.	Cementor	
		Helper	
Bulktrk	<u>256</u>	Driver	<u>Mark Brungardt</u>
		Driver	

CEMENT

Amount 225 sks 65' 35' 16" 370 gal 290 gal 1 3/4" Flo Seal
 Ordered 1255 sks Class A 290 gal 1 3/4" cacl²

Consisting of			
Common	<u>271</u>	<u>5.75</u>	<u>1558.25</u>
Poz. Mix	<u>79</u>	<u>3.00</u>	<u>237.00</u>
Gel.	<u>17</u>	<u>7.00</u>	<u>119.00</u>
Chloride	<u>11</u>	<u>25.00</u>	<u>275.00</u>
Quickset			
	<u>Flo Seal - 56</u>	<u>1.10</u>	<u>61.60</u>
Handling	<u>350</u>	<u>1.00</u>	<u>350.00</u>
Milage	<u>50</u>		<u>700.00</u>
Total \$ <u>4924.05</u>			
<u>984.81</u>			
<u>3939.24</u>		Total	<u>3300.85</u>

DEPTH of Job 730'

Reference:	<u>Pump Charge</u>	<u>430.00</u>
<u>50</u>	<u>Milage</u>	<u>112.50</u>
<u>8 7/8</u>	<u>Top Rubber Plug</u>	<u>83.00</u>
	<u>430' at .39</u>	<u>167.70</u>
	Total	793.20

Remarks: Cmt 4 7/8 Surface Csg with 225 sks 65' 35' 16"
gal 370 cacl² 1 3/4" Flo Seal & 100 sks Class 290 gal
370 cacl² Drop Plug Displace 43.7 GAL Land
Plug Did not circulate cmt, Top off with 25 sks
Rel 10% A 370 cacl² 290 gal Cmt to surface

Floating Equipment

<u>1-8 7/8 Saw Tooth Guide Shoe</u>	<u>258.00</u>
<u>1-8 7/8 AFU Insert</u>	
<u>2-8 7/8 Centralizers</u>	
<u>1-8 7/8 Cement Basket</u>	<u>180.00</u>
<u>1-Thread Lock</u>	
	<u>830.00</u>

RECEIVED
 STATE CORPORATION COM.
 SEP 20 2003
 CONSERVATION DIVISION
 Wichita, Kansas

ORIGINAL

terms and conditions, "Allied" shall mean Allied Cementing Co., Inc., and "Customer" shall refer to the front of this contract, as applicable. "100" relates to the services described on the front side of the material of this contract. If satisfactory credit has been established, the terms of payment for the job and payments of this contract, as applicable, shall be and hereby is deemed to be from the "CUSTOMER" or at the option of "ALLIED" shall be provided for the maximum rate of interest that should be provided at a rate of 18 percent per annum until payment in 30 days from the completion of the job and/or delivery of the merchandise for interest on amounts invoiced at the completion of the job and/or delivery of the merchandise. If satisfactory credit has been established, the terms of payment for the job and payments of this contract, as applicable, shall be and hereby is deemed to be from the "CUSTOMER" or at the option of "ALLIED" shall be provided for the maximum rate of interest that should be provided at a rate of 18 percent per annum until payment in 30 days from the completion of the job and/or delivery of the merchandise for interest on amounts invoiced at the completion of the job and/or delivery of the merchandise. If satisfactory credit has been established, the terms of payment for the job and payments of this contract, as applicable, shall be and hereby is deemed to be from the "CUSTOMER" or at the option of "ALLIED" shall be provided for the maximum rate of interest that should be provided at a rate of 18 percent per annum until payment in 30 days from the completion of the job and/or delivery of the merchandise for interest on amounts invoiced at the completion of the job and/or delivery of the merchandise.

GENERAL TERMS AND CONDITIONS
15-833-2875-000-51

JE 913 483-2627

ALLIED CEMENTING COMPANY, INC.
P. O. BOX 31
RUSSELL, KANSAS 67665

TO: Sam Gary Jr., & Associates
1775 Sherman, Suite 1925
Denver, CO 80203

INVOICE NO. 64328
PURCHASE ORDER NO. _____
LEASE NAME Selzer #8-14
DATE 7-3-93

RECEIVED
JUL 12 1993
SAMUEL GARY JR.
& ASSOCIATES INC.

SERVICE AND MATERIALS AS FOLLOWS:

Common 81 sks @\$5.75	\$465.75	
Pozmix 54 sks @\$3.00	162.00	
Gel 8 sks @\$7.00	<u>56.00</u>	\$ 683.75
Handling 135 sks @\$1.00	135.00	
Mileage (50) @\$.04¢ per sk permi	270.00	
Rotary Plug	430.00	
Mi @\$2.25 pmp trk chg	<u>112.50</u>	<u>947.50</u>
	Total	\$1,631.25

07020695

Thank you!

If account CURRENT 20% discount will be allowed ONLY if paid within 30 days from date of invoice.

All Prices Are Net, Payable 30 Days Following Date of Invoice. 1½% Charged Thereafter.

RECEIVED
STATE CORPORATION COMMISSION
SEP 03 1993
7-3-93
CONSERVATION DIVISION
Wichita, Kansas

15-833-20875-0000

ORIGINAL

3-2627, Russell, Kansas
Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812

Phone Ness City 913-798-3843

ALLIED CEMENTING CO., INC.

1262

Home Office P. O. Box 31

Russell, Kansas 67665

NEW

Date	7/13/93	Sec.	8	Twp.	34s	Range	20W	Called Out	6:30	On Location	9:30	Job Start	12:25	Finish	2:30	
Lease	Seizer	Well No.	8-14	Location				Protection 2W 7s E15	County	Comanche	State	KS				

Contractor	H-40 Drilling	
Type Job	Rotary Plug	
Hole Size	7 7/8	T.D. 5380
Csg.	8 5/8 24"	Depth 730
Tbg. Size		Depth
Drill Pipe	4 1/2 16.6	Depth 840
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.		Minimum
Meas Line		Displace
Perf.		

Owner *Same*

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.

Charge To *Sam Gary Jr + Associates*

Street *1775 Sherman Suite 1925*

City *Denver* State *Colo.* *80203*

The above was done to satisfaction and supervision of owner agent or contractor.

Purchase Order No. *Larry G. Benedict*

CEMENT

Amount Ordered *1355Ks 60140 690gcl*

EQUIPMENT

Pumptrk	No. <i>256</i>	Cementer	<i>Max Ball</i>
		Helper	<i>(Car) Holding</i>
Pumptrk	No.	Cementer	
		Helper	
Bulktrk	<i>242</i>	Driver	<i>Mark Brungardt</i>
Bulktrk		Driver	

Consisting of			
Common	<i>81</i>	<i>5.75</i>	<i>465.75</i>
Poz. Mix	<i>54</i>	<i>3.00</i>	<i>162.00</i>
Gel.	<i>8</i>	<i>7.00</i>	<i>56.00</i>
Chloride			
Quickset			

DEPTH of Job		
Reference:	<i>840 # Pump Charge</i>	<i>430.00</i>
	<i>50 # Mileage</i>	<i>112.50</i>
	Sub-Total	
	Total	<i>542.50</i>

Handling	<i>135</i>	<i>1.00</i>	<i>135.00</i>
Mileage	<i>50</i>		<i>270.00</i>
		Sub-Total	
		Total	<i>1088.75</i>

Remarks: *Plug on Rotary 100skts 60140' 690gcl @ 840' 10skts @ 33' 15skts Rat Hole 10skts Mouse Hole*

Floating Equipment

Total \$ *1631.25*

Disc - *326.25*

\$ 1305.00

RECEIVED
STATE CORPORATION COM
SEP 03 1993
7-3-93
CONSERVATION DIVISION
Wichita, Kansas