

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 South Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-03,464-00-00

LEASE NAME HOFFMAN "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER #6 (SE NW SE SW)

825 Ft. from S Section Line

1815 Ft. from W Section Line

LEASE OPERATOR John O. Farmer, Inc.

SEC. 7 TWP. 16S RGE. 13 XXXXXX (W)

ADDRESS P.O. Box 352, Russell, KS 67665

COUNTY Barton

PHONE# (785) 483-3144 OPERATORS LICENSE NO. 5135

Date Well Completed 9-2-38

Plugging Commenced 7:30 A.M., 6-28-01

Plugging Completed 10:30 A.M., 6-28-01

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by _____ (District #4) _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? (Not available)

Producing Formation Topeka & Lansing Depth to Top 2794' Bottom 3295' T.D. 3363'

P.B.T.D. 3302'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka & Lansing	2794'	3295'		10-3/4"	643'	-0-
				7"	3346'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plug #1 @ 2460' w/90 sks. - 4 sks. hulls Tied to 7" - pumped 80 sks. - 10 sks. down backside

Plug #2 @ 1600' w/90 sks. - 2 sks. hulls The casing was perforated 2 shots @ 1600' and 2 shots @ 900' prior to cementing.

Plug #3 @ 900' w/100 sks. - 1 sk. hulls

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.


STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III XXXXXXXXXXXXXXXXXXXXXXXXXXXX (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 20 01



Margaret A. Schulte
Notary Public
Margaret A. Schulte

Form CP-4
Revised 05-88

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 5 2001
7-5-01
CONSERVATION DIVISION

OR

ALLIED CEMENTING CO., INC. 6253

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>6-28-01</u>	SEC. <u>7</u>	TWP. <u>16</u>	RANGE <u>13</u>	CALLED OUT <u>6:00 AM</u>	ON LOCATION <u>7:00 AM</u>	JOB START <u>7:30 AM</u>	JOB FINISH <u>10:30 AM</u>
LEASE <u>H&D ROAD</u>		WELL # <u>1-6</u>		LOCATION <u>Russell Still</u>		COUNTY <u>Barber</u>	STATE <u>KANSAS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>25 2-1/2"</u>			

CONTRACTOR Express Well Service OWNER Same

TYPE OF JOB: <u>Plug</u>	
HOLE SIZE	T.D.
CASING SIZE <u>7"</u>	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT	AMOUNT ORDERED <u>4.5 cu yd</u>
	<u>10% Gel</u>
	<u>7 Halls</u>
COMMON	@
POZMIX	@
GEL	@ <u>18%</u>
CHLORIDE	@
	@
	@
	@
HANDLING	@
MILEAGE	@

COPY

EQUIPMENT

PUMP TRUCK CEMENTER	
# <u>177</u> HELPER <u>Rm</u>	
BULK TRUCK	
# DRIVER	
BULK TRUCK	
# <u>254</u> DRIVER <u>Showe</u>	
TOTAL	

REMARKS:

1st Plug 2400 90SK 4 Halls
2nd Plug 1600 90SK 2 Halls
3rd Plug 900 100SK 1 Hall
Tried 5" to 7" Pumped back
10SKs Down Backside

DEPTH OF JOB	
PUMP TRUCK CHARGE	
EXTRA FOOTAGE	@
MILEAGE	@
PLUG	@
	@
	@
TOTAL	

CHARGE TO: J.O. Farmer

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@
	@
	@
	@
	@
TOTAL	

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 RECEIVED
 KANSAS CORPORATION COMMISSION

JUL 5 2001

CONSERVATION DIVISION

