

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Comanche County, Sec. 7 Twp. 34S Rge. 20 (X)(W) (W)
Location as "NE/CNW%SW%" or footage from lines C SW
Lease Owner Cleary Petroleum Corporation
Lease Name Schumacher Well No. 1-7
Office Address 310 Kermac Building, Oklahoma City, Oklahoma 73102
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed January 22, 1972
Application for plugging filed January 22, 1972
Application for plugging approved January 22, 1972
Plugging commenced January 22, 1972
Plugging completed January 22, 1972
Reason for abandonment of well or producing formation No Productible Zone.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	614	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud, pushed plug to 600 feet and spotted 35 sacks cement. Filled hole with mud, pushed plug to 40 feet and capped with 10 sacks cement to base of well cellar. Plugged rat hole and mouse hole. Job complete at 11:30 AM January 22, 1972.

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Ben E. Unruh (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh
Box 1164, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of February, 19 72

My commission expires July 8, 1974

George A. [Signature]
Notary Public.

15-833-28114-0000
WELL LOG

COMPANY Cleary Petroleum Company

SEC. 7 T. 34S R. 20W

FARM Schumacher NO. 1-7

LOC. SW/4


TOTAL DEPTH 5480'

COUNTY Comanche, Kansas

COMM. 1-5-72 COMP. 1-22-72

CONTRACTOR Garvey Drilling Company

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1972
CONSERVATION DIVISION
Wichita, Kansas



CASING
20" @ 43' w/4 1/2 yds.
8 5/8" @ 614' w/400sx

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 300' Sand & Red Bed
- 781' Red Bed
- 1131' Shale
- 1850' Shale & Shells
- 2179' Shale
- 2312' Lime & Shale
- 3945' Lime
- 4030' Lime & Shale
- 4402' Lime
- 4483' Shale
- 4520' Lime
- 5100' Lime & Shale
- 5157' Lime
- 5280' Lime & Shale
- 5317' Lime
- 5400' Lime & Sand
- 5410' Lime
- 5480' Lime
- 5480' RTD

State of Kansas }
County of Barton } ss

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Schumacher No. 1-7 well.

Subscribed and sworn to before me this 25th day of January 19 72.

Commission Expires: July 8, 1974

Charlene Marker
James A. Williams
NOTARY PUBLIC