

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Dorby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117 #)

API NUMBER 15-033-20,555-0000

LEASE NAME Selzer

WELL NUMBER A#2

3300 Ft. from S Section 1

660 Ft. from E Section 1

SEC. 3 TWP 34 RGE. 20 (X) (W)

COUNTY Comanche

Date Well Completed 4-7-82

Plugging Commenced 5-28-93

Plugging Completed 8:45 AM,

TYPE OR PRINT
NOTICE: Fill out complotoly
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bishop Operating Co., Inc.

ADDRESS P.O. Box 1807, Hutchinson, Kansas 67504

PHONE# (316) 662-6445 OPERATORS LICENSE NO. 30972

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-28-93 (d:

by Richard Lacey (KCC District Agent's Name

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation KC Depth to Top 4742 Bottom 4746 T.D. 4816

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	731	0
				5 1/2	4812	3296

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from ___ feet to ___ feet each
Bottom Plug: Sanded to 4690 & bailed 5 sx cement.

Top Plug: Pumped 300 lb Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lb Hulls, Wiper plug, 125 sx Cement, 60/40 with 6% Gel. Had maximum pressure of 500 lbs, and 350 lbs shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bishop Operating Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss. 6-2-93


Gary G. Burke

(Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 1 day of June, 19 93



Anna K. Burke
Notary Public

My Commission Expires: 4-30-96