

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Comanche SEC. 3 TWP 34 S RGE. 20 W  
 Location as in quarters or footage from lines:  
1980 FSL 1880 FEL


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Cities Service Company  
 Lease Name Selzer Well No. B-1  
 Office Address 800 Sutton Place-209 E. William Bldg.-Wichita, KS  
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
 Date Well Completed 4-18-82  
 Application for plugging filed 12-1-82  
 Plugging commenced 12-15-82  
 Plugging completed 12-20-82  
 Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 5245

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				20	43	None
				8 5/8	719	None
				5 1/2	4839	3666

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged back at 4,805  
Sand from 4,805 to 4,700  
5 sacks cement with dump bailer from 4,700 to 4,670  
Pumped in 3 sacks hulls - 20 sacks jell - 70 sacks cement - 15 sacks jell  
1 sack hulls - Drop plug. 120 sacks 50-50 POZ - 2% Jell - 3% C. C.  
Plugged down at 1:00. Press - Shut in - 3:50

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Edna R. Morgenstern (employee of ~~owner~~) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Edna R. Morgenstern  
Medicine Lodge, Kas.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of Dec., 19 82.

Jessie A. [Signature]  
 STATE NOTARY PUBLIC

My Commission expires: April 4, 1986

DEC 27 1982  
 12-27-82  
 CONSERVATION DIVISION  
 Wichita Kansas