

1 020586

7-4

API NUMBER 15- 033-20,875-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 8, T. 34 S, R. 20 W/E

1050 feet from S section line

2350 feet from W & X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3882

Lease Name Selzer Well # 8-14

Operator: Samuel Gary Jr. & Assoc.
Name &

County Comanche 177.77

Address 1775 Sherman St., Ste. 1925
Denver, CO 80203

Well Total Depth 5470 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 740

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-40 Drilling, Inc. License Number 30692

Address 251 N. Water, Ste. 10, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 4 Month: 7 Year: 1993

Plugging proposal received from Jim Johnson

(company name) H-40 Drilling, Inc. (phone) 316-263-2043

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 812'

1st plug at 830' with 100 sx cement,

2nd plug at 40' with 10 sx cement,

3rd plug to circulate rathole with 15 sx cement,

4th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: _____ Day: 4 Month: 7 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 840' with 100 sx cement,

2nd plug at 40' with 40 sx cement,

3rd plug to circulate rathole with 15 sx cement,

4th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

JUL - 9 1993

(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

7-9-93
CONSERVATION DIVISION
Wichita, Kansas

DATE JUL 19 1993

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 38140

FOR KCC USE:

EFFECTIVE DATE: 5/30/93

DISTRICT # 1
SGA? Yes... No

Must be approved by the K.C.C. five (5) days prior to commencing well.

State of Kansas

NOTICE OF INTENTION TO DRILL (AMENDED)

FORM C-1 7/91
FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Expected Spud Date JUNE 15, 1993
month day year

Spot NE - SE - SW Sec 8 Twp 34 S, Rg 20 X East

OPERATOR: License # 3882
Name: SAMUEL GARY JR. & ASSOC.
Address: 1775 SHERMAN STREET, SUITE 1925.
City/State/Zip: DENVER, CO 80203
Contact Person: CRAIG AMBLER
Phone: 303) 831-4673
267-4521

1050 feet from South / North line of Section
2350 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: COMANCHE

Lease Name: SELZER Well #: 8-14

Field Name: WILDCAT

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): MORROW

Nearest lease or unit boundary: 1050 FT

Ground Surface Elevation: 1761 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 100

Depth to bottom of usable water: 180

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 675'

Length of Conductor pipe required: 40'

Projected Total Depth: 5500

Formation at Total Depth: MISSISSIPPIAN

Water Source for Drilling Operations:

X well farm pond other

CONTRACTOR: License #: 3882
Name: [Redacted]

Well Drilled For: Well Class: Type Equipment:

X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWWO Disposal X Wildcat Cable
Seismic; # of Holes Other
Other

If OWWO: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location: EX. 11-25-92

Will Cores Be Taken?: yes X no

If yes, proposed zone:

Min. 200' Alt. I

AFFIDAVIT

Pusher Jim Johnson
SPUD DATE 6-24-1993 INIT. GB
LENGTH SURFACE PLANNED 675'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 7-7 CONDUCTOR
ANHYDRITE T- B- 740 ELEVATION

TD 5470 FORMATION

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ 830 Ft. W/ SX

Hug./Council @ 840 Ft. W/ SX

Anhydrite Base @ 830 Ft. W/ 100 SX

1/2 Base Anhy. @ 830 Ft. W/ SX

1/2, 1/2 Plug @ 830 Ft. W/ SX

Bottom Surface @ 40 Ft. W/ 40 3/4 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond)
Hauling

TECHNICIAN GB DATE 7-2-93

TYPE OF CEMENT 60/40 pas 69s

STARTING TIME : (AM/PM) DATE

COMPLETION TIME : (AM/PM) DATE 7-4-93

CEMENT COMPANY Appl

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1993
NATURAL GAS DIVISION
Wichita, Kansas