

1041409

STATE CORPORATION COMMISSION

API NUMBER 15-033-21,104 - 0000
175' W SE SW NE SEC. 3, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1825 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LESTER WELL # 1-3

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 203.45

OPERATOR LICENSE # 5144

WELL TOTAL DEPTH 6260 FEET

OPERATOR: MULL DRILLING COMPANY PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 2758 SURFACE CASING: SIZE 8 5/8" @ 667' WITH SX

ADDRESS WICHITA, KS 67201-2758 CONDUCTOR CSG: SIZE 20" @ 65'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING LICENSE NUMBER 5929

ADDRESS 100 S MAIN, SUITE 410 WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 2:00 AM DAY: 24 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM JOE LIVINGSTON

RECEIVED
STATE CORPORATION COMMISSION

(COMPANY NAME) DUKE DRILLING (PHONE) 316-267-1331

AUG - 8 2000

WERE:

1ST PLUG AT 6440' WITH 40 SX CEMENT. 2ND PLUG AT 900' WITH 50 SX CEMENT.
3RD PLUG AT 690' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG TO
CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

8-8-00
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:00 AM DAY: 24 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 6440' WITH 40 SX CEMENT. 2ND PLUG AT 900' WITH 50 SX CEMENT.
3RD PLUG AT 690' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG TO
CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

DATE 8/10/00
WV. NO. 1060334

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

[Handwritten signature]
[Handwritten initials]