

To: 1051615 2-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,514-00-02 10P

C NE NE, SEC. 3, T 34 S, R 20 W/EX
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30972
Operator: Bishop Operating Co., Inc.
Name & Address P.O. Box 1807
Hutchinson, KS 67504

Lease Name Selzer A Well # 1
County Comanche
Well Total Depth 4805 156.16 feet
Conductor Pipe: Size 13 3/8 feet 43
Surface Casing: Size 8 5/8" feet 730

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 2 Month: 2 Year: 19 93

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4804' w/200 sx cement, PBTD 4775', Perfs at 4744-50'
1st plug sand back to 4680' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 9 a.m. Day: 2 Month: 2 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 4680' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released .8 5/8"
wiper plug and pumped 125 sx cement.
Maximum pressure 660 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3324' of 5 1/2" casing.
(Additional description is necessary, use BACK of this form.)

INVOICED
I (did / ~~did not~~) observe this plugging.
DATE 3-3-93
INV. NO. 37432

Signed Richard W. Tracy
(TECHNICIAN)