

23

1090958

TO: STATE CORPORATION COMMISSION 10-9 API NUMBER 15-033-20,973-0000 W/2 E/2 SW SEC. 19, T 34 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BARBY WELL # 1-19

TECHNICIAN'S PLUGGING REPORT COUNTY COMANCHE

OPERATOR LICENSE # 6875 WELL TOTAL DEPTH 7229 234.95 FEET

OPERATOR: MARMIK OIL COMPANY PRODUCTION CSG: SIZE " FEET

NAME AND 8500 W BOWLES AVE, SUITE 307 SURFACE CASING: SIZE 8 5/8 " FEET 644'

ADDRESS LITTLETON, CO 80123

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ABERCROMBIE RTD LICENSE NUMBER 30684

ADDRESS 150 N MAIN, STE 801, WICHITA, KS 67202-1383

COMPANY TO PLUG AT: HOUR: 11:00 PM DAY: 08 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM BILL CRAIG

(COMPANY NAME) ABERCROMBIE RTD (PHONE) 316-262-1841

WERE:

1ST PLUG AT 7114' WITH 40 SX CEMENT, 2ND PLUG AT 950' WITH 40 SX CEMENT,

3RD PLUG AT 670' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 7:00 AM DAY: 09 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 7114' WITH 40 SX CEMENT, 2ND PLUG AT 950' WITH 40 SX CEMENT,

3RD PLUG AT 670' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED (TECHNICIAN) FORM CP-2/3

10-19-98 60120

10-19-98 11:11 AM RECEIVED BY STEVE MIDDLETON

Handwritten signature