

To: 1051676
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-15

API NUMBER 15-033-20,302-0000 Docket #E-19,726

C NE NE, SEC. 23, T. 34 S, R. 20 W/4E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Operator: Bishop Operating Company, Inc.

Name & Address: P.O. Box 1807

Hutchinson, KS 67504

Lease Name G.C. Lemon Well # 8

County Comanche 173.06

Well Total Depth 5325 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 785

Abandoned Oil Well Gas Well _____ Input Well SWD Well _____ D&A _____

DUAL COMPLETION

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 10 a.m. Day: 15 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5322' w/150 sx cement, Perfs at 5181-5206'

1st plug sand back to 5090' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls

and 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 15 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 5090' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 750 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 6-24-93

37992

Signed Richard W. Lacer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

JUN 18 1993

6-18-93 CONSERVATION DIVISION Wichita, Kansas