

FOR IMAGING ONLY - PLUG DATE EXCEEDS  
5 YEAR BILLING CUTOFF. 7/18/14  
CKM

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19396-00-00  
Spot: W2W2E2NE Sec/Twnshp/Rge: 28-34S-12E  
3960 feet from S Section Line, 1125 feet from E Section Line  
Lease Name: BROOKS Well #: 19  
County: CHAUTAUQUA Total Vertical Depth: 1110 feet

Operator License No.: 33157  
Op Name: R. D. ENERGY, INC.  
Address: 905 N MONTGOMERY  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1110		
SURF	7	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2008 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 50' plug at 700' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 03/26/2008 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1100' and spotted 15 sack plug. Pulled up to 700' and spotted 10 sack plug. Pulled 1" out and perforated casing at 350'. Ran back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 95 sacks of cement were used to plug this well.

Perfs:

RECEIVED

JUL 15 2014

KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

KCC WICHITA

JUL 17 2014

RECEIVED

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)