

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-40221-00-00  
Spot: SESENE Sec/Twnshp/Rge: 31-24S-4E  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MCGILL Well #: 10  
County: BUTLER Total Vertical Depth: 2691 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2676		35 SX
SURF	15.5	77		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2014 12:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: STEVEN KILE Company: PHILLIPS WELL SERVICE, INC. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/08/2014 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

4/7/2014 RAN TBG IN 2652' AND CONSOLIDATED SPOT 50 SXS 60/40 POZMIX + 4% CC. LET CMT SET 1 HR AND RAN A WIRELINE IN AND TAGGED CEMENT @ 2428'. DYNA-LOG PERFORATED 4 HOLES @ 250'. PHILLIPS RAN 10 JTS OF TUBING IN THE HOLE AND PACKED IT OFF. CONSOLIDATED PUMPED 416 SXS OF 60/40 POZMIX AND CIRCULATED CEMENT TO SURFACE. SDON. 4/8/2014 RAN TUBING IN THE HOLE AND TAGGED CEMENT @ 85'. HAD REDDY MIX FILL THE 7" W/CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2676	2691		

KCC WICHITA  
JUL 15 2014  
RECEIVED

Remarks: CONSOLIDATED

Plugged through:

District: 02

Signed *Patrick Shields*  
7.18.14 CKM (TECHNICIAN)

*JK*