

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40439-00-00
Spot: SESWSWSW Sec/Twnshp/Rge: 31-24S-4E
225 feet from S Section Line, 600 feet from W Section Line
Lease Name: MAXWELL / MCGILL 2 Well #: 8
County: BUTLER Total Vertical Depth: 2704 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2666		0 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2014 12:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVEN W. KILE Company: PHILLIPS WELL SERVICE, INC. Phone: (316) 322-5776

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 03/11/2014 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report: _____ Perfs: _____


3/10/2014 PHILILPS WELL SERVICE RIH W/TBG TO 2630'. CONSOLIDATED PUMPED 30 SXS OF 60/40 POZMIX + 4% GEL + 4% CC + CELLOFLAKE. WAIT 45 MINUTES AND TAGGED CEMENT @ 2520'. DYNOLOG PERFORATED 4 HOLES @ 250'. HAD GOOD CIRCULATION BETWEEN THE 7" AND 15 1/2" CSGS. RIH AND PERFORATE 4 HOLES @ 1125'. CONSOLIDATED SPOT 20 SKS CMT AND WAIT 45 MINUTES. TRIED TO TAG CEMENT AND IT WAS GONE. SPOT 20 SKS MORE OF CEMENT AND LET SET 45 MIN. STILL NO FILLUP. PUMPED 230 SXS 60/40 POZMIX + 4% GEL + 4% CC + CELLOFLAKE DOWN THE 7" AND BETWEEN THE 7" AND 15 1/2" TO SURFACE. SDON. 3-11-2014 TAGGED CEMENT 45' DOWN THE 7" FILLED TO SURFACE W/22 SXS CEMENT. RAN 1" BETWEEN THE 7" AND 15 1/2" TO 60' AND FILLED TO SURFACE W/ 22 SKS CEMENT. JOB COMPELTE.

KCC WICHITA
JUL 15 2014
RECEIVED

Remarks: CONSOLIDATED

Plugged through: _____

District: 02

Signed 
7.18.14 CKM (TECHNICIAN)

JK