

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19322-00-00
Spot: NWSESE Sec/Twnshp/Rge: 35-25S-4E
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: RICE-PARMELEE Well #: 4
County: BUTLER Total Vertical Depth: 2424 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2408		0 SX
SURF	8.625	200		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2014 12:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DALLAS FLOWERS, CROW Company: IRON HORSE WELL SERVICE LLC Phone: (316) 323-3869

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 04/02/2014 12:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report: _____ Perfs: _____


PU RIH W/2400', 2 3/8" TUBING. CONSOLIDATED CEMENTED DOWN TUBING W/35 SXS CLASS A, 4 % GEL. CEMENT TOP 1887', POH W/TBG. RIH W/WIRELINE PERFORATED @ 250', POH W/WIRELINE, RIH W/250' TBG, CONSOLIDATED CEMENTED DOWN TBG W/135 SXS, 60/40POZ MIX, 4% GEL, CIRCUALTED OUTSIDE CSG TO SURFACE, CMT HELD, TICKET #46259.

Remarks: CONSOLIDATED CEMENTING

Plugged through: TBG

District: 02

Signed



7-18-14 CKM (TECHNICIAN)

KCC WICHITA
JUL 15 2014
RECEIVED

14