

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06512-00-00
Spot: SWNENE Sec/Twnshp/Rge: 26-18S-10W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: ROELFS H CULBERTSON Well #: 1
County: RICE Total Vertical Depth: 3221 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2980		
PROD	5.5	3178		90 SX
SURF	8.625	280		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2014 11:00 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Revd. from: KENT STRUBE Company: HARTMAN OIL Phone: (620) 786-4161

Proposed Plugging Method: PER KCC RULES & REGS. HARTMAN OIL CO. HAS NEVER PRODUCED THIS WELL. THIS WELL WAS A DENIED TA WELL.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/02/2014 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, WELL HAS 3.5" TUBING STUCK - WORKED LOOSE AND GOT PULLED OUT - HAD TO MILL SOME TO GET PULLED OUT. SET CIBP AT 2980'. ATTEMPTED TO TEST LANSING A AND B -KC ZONES, DECIDED TO PLUG WELL. RUN TUBING TO 2820' AND PUMP 50 SXS COMMON CEMENT, LET SET AWHILE AND TAGGED AT 2438'. PERFORATE AT 1200' AND PUMP 35 SXS COMMON CEMENT, LET SET AWHILE AND TAGGED AT 1060'. PERFORATE AT 850' AND 330'. RUN TUBING BACK IN TO 850' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 330' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2892	2896	CSG	
2872	2878	CSG	

KCC WICHITA
JUL 15 2014
RECEIVED

Remarks: LOG TECH OF KS #8052. COPELAND TICKET #C-42710. DENIED TA

Plugged through:

District: 02

Signed Virgil Clothier
7-18-14 CKM (TECHNICIAN)

JK