

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-20342-00-00  
Spot: NENWNWSE Sec/Twnshp/Rge: 15-34S-12E  
2467 feet from S Section Line, 2199 feet from E Section Line  
Lease Name: CONLEY Well #: 6  
County: CHAUTAUQUA Total Vertical Depth: 940 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1009		25 SX
SURF	10	12		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2014 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 05/07/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 900' gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 180 sacks of cement were used to plug this well.

RECEIVED  
JUL 15 2014  
KCC Chanute Dist. #3

DS

KCC WICHITA

JUL 17 2014

RECEIVED

Remarks: WELL PLUGGED DUE TO PLUGGING AGGREEMENT WITH THE KCC.

Plugged through:

District: 03

Signed [Signature]  
7.18.14 CKM (TECHNICIAN)