

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40144-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 1-35S-11E
4139 feet from S Section Line, 4347 feet from E Section Line
Lease Name: BECK Well #: 31
County: CHAUTAUQUA Total Vertical Depth: 1185 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	870		0 SX
PROD	6.25	885		
SURF	10	7		0 SX
SURF	10	20		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/20/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1000' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 15 sack plug. Pulled 1" and topped well off. A total of 158 sacks of cement were used to plug this well.

RECEIVED
JUL 15 2014
KCC Chanute Dist. #3

DS

KCC WICHITA
JUL 17 2014
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed 
7-18-14 CKM (TECHNICIAN)