

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-40284-00-00  
Spot: NENWNENE Sec/Twnshp/Rge: 36-34S-11E  
5120 feet from S Section Line, 770 feet from E Section Line  
Lease Name: DUNHAM-LEMMON Well #: 4  
County: CHAUTAUQUA Total Vertical Depth: 1178 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	892		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2014 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/13/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 950' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 120 sacks of cement were used to plug this well.

RECEIVED

JUL 15 2014

KCC Chanute Dist. #3

DS

KCC WICHITA

JUL 17 2014

RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed



7-18-14 CKM

(TECHNICIAN)