

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-19052-00-01
Spot: SESESW Sec/Twnshp/Rge: 1-21S-13E
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PAXSON Well #: 1
County: COFFEY Total Vertical Depth: 2291 feet

Operator License No.: 32811
Op Name: OSAGE RESOURCES, LLC
Address: 6209 N K61 HWY
HUTCHINSON, KS 67502

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	600		
SURF	10.75	97		

Well Type: SWD UIC Docket No: D16103.0 Date/Time to Plug: 07/09/2014 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ td. 50' cement plug @ 700' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/09/2014 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 704' hit solid could not drill thru, pumped 50 sxs. Cement pulled pipe to 250' pumped 54 sxs cement to surface gel spacer between cement plugs.

Perfs:

RECEIVED
JUL 14 2014
KCC Chanute Dist. #3
MH

KCC WICHITA
JUL 17 2014
RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed Micho Doffner
cc: UIC ✓ (TECHNICIAN)
7/18/21 ckm

Hurricane Services, Inc.
 3613 A Y Road
 Madison, KS 66860
 Office # 620-437-2661
 Brad Cell # 620-437-6765



HURRICANE SERVICES INC
 OILFIELD SERVICES
 MADISON, KANSAS

Ticket Number 100500
 Location Madison
 Foreman Brad Butler

3195L SWSE SES 40
 2977EL

Copy for Mike

Cement Service ticket

Date	Customer #	Well Name & Number	Sec./Township/Range	County
7-9-14		Paxson #1	1-23-14	Coffey
Customer		Mailing Address	City	State Zip
Osage Resources				

Job Type:	Plug To Abandon			Truck #	Driver
Hole Size:	Casing Size: 7"	Displacement:	201	Jerry	
Hole Depth: 2291'	Casing Weight:	Displacement PSI:	202	Bryan	
Bridge Plug:	Tubing:	Cement Left in Casing:	106	Kelly	
Packer:	PBTD:				

Quantity Or Units	Description of Services or Product	Pump charge	
20	Mileage	\$3.25/Mile	790.00 65.00
104 SACKS 358 lbs	60/40 Pozmix cement Gel 4%	12.00 .30	1248.00 107.40
200 lbs.	Gel > Spacer between Plugs	.30	60.00
4 hrs.	WATER TRUCK	84.00	336.00
	Rental on Wash Head (swivel)		50.00
Tons	Bulk Truck > minimum charge	1.50	300.00
20 miles	Truck #11	1.50	30.00
	Plugs		
		Subtotal	2986.40
	6.15%	Sales Tax	87.05
		Estimated Total	3073.45

Remarks: Well was once plugged - then Recapped - ran tubing down well, Taped at 704'.
 Rig up to Tubing, Broke circulation - we were unable to wash or drill through Bridge - Possibly B.P.
 got orders to go ahead Plug well by Mike Heffner

KCC WICHITA

50 SKS at 700' JUL 17 2014
 54 SKS at 250' To Surface RECEIVED

Note: Gel Spacer between cement Plugs

Witnessed by Mike Heffner - Rep for KCC
 Customer Signature