

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21944-00-00
Spot: SWSE Sec/Twnshp/Rge: 4-34S-6W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: KATE 3406 Well #: 1-4
County: HARPER Total Vertical Depth: 5107 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4427		
CIBP	5.5	4675		
COND	16	40		10 SX
PROD	5.5	5102	1800	360 SX
SURF	8.625	631		405 SX
TI	2.875	4809		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2014 6:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: CODY YATES Company: SANDRIDGE EXPL Phone: _____

Proposed Plugging Method: CIBP @ 4427 & 5 SXS. REC PIPE. 50 SXS @ 1050', 50 SXS @ 700'. CIRC CEMENT 60'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 07/07/2014 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4427 & CAPPED WITH 5 SXS CEMENT. RECOVERED 1800' OF 5 1/2" CASING AND LAYED DOWN. RAN 2 7/8" TUBING TO 1050' SPOTTED 50 SXS CEMENT. PULLED TUBING TO 700' & SPOTTED 50 SXS CEMENT. PULLED TUBING TO 300' & CIRCULATED CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4702	4710	CSG	
4485	4514	CSG	

KCC WICHITA
JUL 15 2014
RECEIVED

Remarks: COPELAND CEMENT COMMON #40887

Plugged through: TBG

District: 02

Signed _____

7-18-14 CKM

(TECHNICIAN)