

7-11-88 DOCKET D20,482

To: 1 051070(B)  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,457-00-01  
NW SE, SEC. 1, T 34 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6528

Operator: R.J. Patrick Operating  
Name & Address: Box 1314  
Liberal, KS 67901

1980 feet from S section line  
1980 feet from E section line

Lease Name Wesley Girk Well # 2  
County Comanche 156.91

Well Total Depth 4828 feet

Conductor Pipe: Size 20" feet 60

Surface Casing: Size 8 5/8" feet 668

Abandoned Oil Well ~~SC~~ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor: Midwest Casing Pulling License Number 6497

Address: Box F, Sublette, KS 67877

Company to plug at: Hour: 11:30 a.m. Day: 11 Month: 7 Year: 1988

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling

were: 4 1/2" at 4828' PBTD 4807' Perfs at 4777-80'

RECEIVED  
STATE CORPORATION COMMISSION 8349

1st plug pump 20 sx cement and 2 sx hulls to 4600'

2nd plug pump 40 sx cement at 880'

3rd plug pump 40 sx cement at 680'

4th plug pump 10 sx cement at 40'

1111 21 1988  
7-21-88  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 11 Month: 7 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx common cement and 2 sx hulls to 4600'

2nd plug pump 40 sx cement at 880'

3rd plug pump 40 sx cement at 680'

4th plug pump 10 sx cement at 40'

Remarks: Used common cement by Midwest Casing Pulling. Recovered 3430' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (did / did not) observe this plugging.  
XXXXXX

DATE 7-26-88

Signed Richard G. Lacey (TECHNICIAN)

INV. NO. 21670 SEP 12 1988  
7-11

SWD