

1 010006

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,748-0000

SE NE NE, SEC. 3, T 30s, R 13 (W) X

4425 feet from S section line

125 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5035

Lease Name Tregellas Well # 4

Operator: Aladdin Petroleum Corp.

County Barber 158.77

Name & Address 809 Petroleum Building

Well Total Depth 4885 feet

Wichita, KS 67202

Conductor Pipe: Size 13 3/8 feet 243

Surface Casing: Size 8 5/8 feet 955

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 am Day: 12 Month: July Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4638' Perfs at 4502-10'; 4372-92'

1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:20 am Day: 12 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 1200 psi and shut in 700 psi

Remarks: Recovered 3085' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Aladdin. (if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 7-24-85

TRIV. NO. 9080

Signed Paul A. Luthi (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUL 22 1985 CONSERVATION DIVISION