

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21323-00-00
Spot: E2NENE Sec/Twnshp/Rge: 21-32S-17W
670 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: MUSTANG LAND AND CAT Well Number: 1
County: COMANCHE Total Vertical Depth: 2750 feet

Operator License No.: 31093
Op Name: BECKER OIL CORPORATION
Address: 122 E. GRAND, STE. 212
PONCA CITY, OK 74601

Conductor Pipe: Size feet: 8 8 3/8
Surface Casing: Size 8.625 feet: 688
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 07/05/2002 5:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Revd. from: GALEN ROACH Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1000' WITH 50 SX CMT. 2ND PLUG AT 710' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 30 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 07/05/2002 8:15 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 1000' WITH 50 SX CMT. 2ND PLUG AT 710' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 30 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED
JUL 19 2002
7-19-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

INVOICED JUL 16 2002

DATE 7-19-02

INV. NO. 2003060068

Form 2/3