

5-4-88

To: 1 040093  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,245 -0000  
C NW NE, SEC. 21, T 32 S, R 17 W/XX  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5171

Lease Name Belcher "A" Well # 2  
County Comanche 191.10  
Well Total Depth 5880 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 628

Operator: TXO Production Corporation  
Name & Address 125 North Market, Suite 1000  
Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:45 a.m. Day: 4 Month: 5 Year: 19 88

Plugging proposal received from Richard Wortman

(company name) TXO Production Corporation (phone) 316-886-5605

were: 5 1/2" at 5255' PBT 5255' Perfs at 5140-44' Elevation 2084' GL

1st plug sand back to 5090' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, and 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p.m. Day: 4 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 5090' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

5-13-88  
MAY 13 1988

Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3315' of casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-17-88

INV. NO. 20666

5-4

Signed Stephen Pfeifer (TECHNICIAN)