

1051916  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-033-20,230-00-C1  
C NE NE, SEC. 21, T 32 S, R 17 W/E  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30157  
Operator: B R G Petroleum, Inc.  
Name & Address 7134 S. Yale, #600  
Tulsa, OK 74136

Lease Name Belcher Well # A-1  
County Comanche 193.38  
Well Total Depth 5950 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 590

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 11 Month: 4 Year: 1995

Plugging proposal received from Richard McIntyre

(company name) Mikes Testing & Salvage, Inc. (phone) 316-938-2943

logs: 5 1/2" at 5205' w/175 sx cement, Perfs at 5140-42, 4081-86'

1st plug sand back to 4050' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1110' with 50 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 40' with 20 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 11 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement on top of sand through bailer. Spotted cement through casing with gel spacers in between.

2nd plug at 1110' with 50 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 40' with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2750' of 5 1/2" casing.  
(additional description is necessary, use BACK of this form.)

(did / observe this plugging.

DATE 4-21-95

INV. NO. 42652

Signed Richard M. Lucey  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 14 1995  
4-14-95  
CONSERVATION DIVISION  
WICHITA, KS