

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19017-00-00
Spot: NE NW SE Sec/Twnshp/Rge: 30-20S-12W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: FLANDERS Well Number: 3
County: BARTON Total Vertical Depth: 3547 feet

Operator License No.: 6458
Operator Name: POOR BOY CORPORATION
Address: 582 S E 50TH AVE
ELLINWOOD, KS 67526

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 195 275 SXS CMT
Production: Size 5.5 feet: 3488 125 SX CMT 115.28
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2000 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 220 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot casing off at 2235'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/26/2000 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 195' w/275 sxs. 5 1/2' set at 3488'.
Sanded back to 3215' and topped with 5 sxs cement using a dump bailer.
Ran in hole and shot off casing at 2235'.
Rigged up on casing and pulled to 1500'.
Tied onto casing and pumped 110 sxs with 300# hulls.
Pulled up to 700' and spotted 50 sxs with 100# hulls.
Pulled up to 200' and circulated cement with 40 sxs.
Pulled out of the hole. Hole standing full of cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 3 2000
11-3-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 11/6/00

INV. NO. 2001060939

OCT 30 2000

VIRGINIA DRLG

#3 FLANDERS+

30-20-12W S3
NE NW SE

Contr. CO TOOLS

BARTON

County

E 1881DF Comm. 5/22/63 Comp. 8/1/63 IP PMP 25 BOPD + WTR

(ARB 3488-3547)

LOGTops	Depth	Datum
HEER	3086	-1205
BR 1M	3209	-1328
LANS	3224	-1343
ARB	3482	-1601
TD	3547	-1666

Casing


8" 195/275 SX:

5" 3488:

NO TESTS:

CO DD 3547: A 2000 & 600# ROCK
SALT, SWB LD, SWB 5 BO + 12 BW/
NT: POP:

ROLLING GREEN EAST



GEOL: FRANK HAMLIN:

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS