

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23589-00-00
Spot: CNWSWNE Sec/Twnshp/Rge: 30-20S-12W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: FLANDERS Well Number: 4
County: BARTON Total Vertical Depth: 3750 feet

Operator License No.: 4058
Operator Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 690 400 SX CMT
Production: Size 7 feet: 3655 200 SX CMT 121.88
Liner: Size _____ feet:

Well Type: SWD UIC Docket No: D24283.0 Date/Time to Plug: 11/09/2000 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 385 sxs 60/40 pozmix - 10% gel with 500# hulls.
Shot casing at 1525'.

Plugging Proposal Received By: HUBERT DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/09/2000 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Quality Well Service rigged up on 7" casing.
Sanded back to 3160' and topped with 5 sxs cement using dump bailer.
Shot casing at 1525'.
Pulled to 1350'.
Allied Cementing tied onto and pumped 155 sxs with 300# hulls.
Pulled to 725' and tied onto and spotted 50 sxs with 200# hulls.
Pulled to 200' and circulated cement with 180 sxs.
Pulled out of the hole and topped with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION...

NOV 22 2000
11-22-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE

11/29/00

INV. NO.

2001061034

Form CP-2/3

NOV 15 2000


BERGMAN OIL COMPANY
520 UNION CENTER
WICHITA, KS. 67202

INDEPENDENT OIL & GAS SERVICE, INC.

#4 FLANDERS

30-20-12W
NW SW NE

CONTR BERGMAN DRILLING CITY BARTON
GEOL _____ FIELD ROLLING GREEN EAST



ELV 1861 KB SPD 6/18/84 CARD ISSUED 3/21/85 IP SWDW
1856 GL DRLG COMP 6/24/84 ARB OH 3655-3750
API 15-009-23,589

SMP	Top	Depth/Datum
ARB	3487-1626
RTD	3750-1889

10 3/4 " 690 / 400 SX, 7" 3655 / 200 SX
NO CORES OR DSTS RPTD
MICT - CO, (ARB OH), SET 2 3/8 " TBG AT 3640, SWDW - IN-
JECTION RATE SATISFACTORY - NO OTHER INFO RELEASED BY
OPERATOR

INFO RELEASED: 3/26/87 - WAS SWDW - TIGHT HOLE

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS