

Corrected

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04973-00-00
Spot: NESWNE Sec/Twnshp/Rge: 30-20S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: FLANDERS Well Number: 3
County: BARTON Total Vertical Depth: 3503 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 275 275 SX CMT
Production: Size 4.5 feet: 3502 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/02/2000 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: CECIL O'BRATE Company: QUALITY WELL SERVICE, INC. Phone: (316) 275-9231

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot casing at 1480' - 650' - 350'.

Plugging Proposal Received By: CASE MORRIS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/02/2000 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

11-02-2000 - Rigged up and sanded off bottom to 3390' and topped with 5 sxs cement.
Ran in hole and shot casing at 1480' - casing did not free.
Allied Cementing tied onto casing and pumped 70 sxs with 300# hulls and displaced with 15 bbls of water.
Ran back in hole and shot casing at 650' - casing did not free.
Allied Cementing tied onto casing and pumped 30 sxs with 100# hulls and displaced with 5 bbls of water. Shut in for the night.
11-03-2000 - Ran in hole and shot casing loose at 350' - pulled up to 300'.
Allied tied onto and circulated cement with 100 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN) KANSAS CORPORATION COMMISSION

RECORDED
JAN 11 2001 CP-2/3
1-11-01
CONSERVATION DIVISION
WICHITA KS

NOV 03 2000

11-100 MAP NO. _____ SEC. 30-20S-12W. 2

STATE Kans COUNTY Barton: LOC. App NE SW NE

OPER Jay Bergman Oil Co. - Wichita, Kansas FT/FR _____ LINE _____

WELL 3 FARM Flanders FT/FR _____ LINE _____

POOL Rolling Green East ELEV. 1854 GR. 1856 OF 1859 KB

CONT. Co. tools GEOL. Harold Bergman

CO. INT. 3500' Oil Test

F.R. 9-19-63 SPUD 9-21-63 COMP. 11-12-63

TD 3503 FM. Arbuckle PSTD.

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		Arbuckle	3492-3502		20
	I.P. Co P 60 BOPD-NW (Gr NA)				

Casing Record	8 5/8" @275 w/275 sx.	4 1/2" @3502 1/2 w/200 sx.	<i>Data Inc.</i>
---------------	-----------------------	----------------------------	------------------

(KB Spl)

Hb 3072
BL 3194
Lans 3208
Arb 3485
RTD 3500

(KB Log)

Hb 3074 -1215
BL 3197 -1338
LKc 3209 -1350
BKc 3424 -1565
Cg1 3446 -1587
Arb 3486 -1627
LTD 3503 -1644

X