

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04973-00-00
Spot: NESWNE Sec/Twnshp/Rge: 30-20S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: FLANDERS Well Number: 3
County: BARTON Total Vertical Depth: 3503 feet

Operator License No.: 4058
Operator Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 275 275 SX CMT
Production: Size 4.5 feet: 3502 200 SX CMT
Liner: Size _____ feet: _____

11/2

113.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2000 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Shot casing at 1480' - 650' - 350'.

Plugging Proposal Received By: CASE MORRIS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/02/2000 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 251' w/250 sxs. 4 1/2" set at 3470'.
11-02-2000 - Rigged up and sanded off bottom to 3390' and topped with 5 sxs cement.
Ran in hole and shot casing at 1480' - casing did not free.
Allied Cementing tied onto casing and pumped 70 sxs with 300# hulls and displaced with 15 bbls of water.
Ran back in hole and shot casing at 650' - casing did not free.
Allied Cementing tied onto casing and pumped 30 sxs with 100# hulls and displaced with 5 bbls of water. Shut in for the night.
11-03-2000 - Ran in hole and shot casing loose at 350' - pulled up to 300'.
Allied tied onto and circulated cement with 100 sxs.
Pulled casing out of the hole.
Hole standing full of cement.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 11/21/00
INV. NO. 2001061006

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 2000
11-20-00
CONSERVATION DIVISION
Wichita, Kansas

NOV 03 2000