

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19019-00-00
Spot: NENWSW Sec/Twnshp/Rge: 36-20S-13W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: SCHARTZ A Well Number: 2
County: BARTON Total Vertical Depth: 3570 feet

Operator License No.: 5920
Op Name: TE-PE OIL & GAS COMPANY
Address: PO BOX 522
CANTON, KS 67428

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 255 250 SX CMT
Production: Size 5.5 feet: 3569 150 SX CMT
Liner: Size feet:

12/21

116.03

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/21/2000 11:30 AM
Plug Co. License No.: 5920 Plug Co. Name: TE-PE OIL & GAS COMPANY
Proposal Revd. from: BUD BRUNGARDT Company: ALLIED CEMENTING COMPANY Phone: (316) 793-5861

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Prod Perfs at 3348' - 3450'.
CIBP at 3485'.
Squeezed 325' - 602' with 350 sxs in April of 1981.
No record that well was plugged and re-entered.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/21/2000 12:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 5 1/2" and pumped 260 sxs cement with 500# hulls.
Max. P.S.I. 700#. S.I.P. 450#.
8 5/8" annulus 5 sxs cement and pressured to 600#.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 28 2000

12-28-00
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 12/29/00

WVZ NO. 2001061217

DEC 22 2000

GULF OIL CORPORATION
P.O. BOX 12116
OKLAHOMA CITY, OK 73157
CONTR UNKNOWN

#2 SCHATZ "A" "OWWO"

36-20-13W
NE NW SW

CTY BARTON

GEOL _____ FIELD SHAEFFER-ROTHGARN

E 1871 KB CM E 7/1/81 CARD ISSUED 11/19/81 IP P 14 BO & 146 BWPD
LKC 3304-3353 OA

+	+	+
+	+	+
+	+	+

API NOT ASSIGNED

	TOPS	DEPTH	DATUM
ANHY		694	+1177
HEEB		3097	-1226
BR LM		3218	-1347
LANS		3234	-1363
B/KC		3465	-1594
CONG		3476	-1605
ARB		3516	-1645
TD		3570	-1699

OLD INFO: OPERATOR WAS ALPINE OIL, #2
SCHATZ, SPD 4/28/62, SET 8" 255 &
5" 3569, COMPLETED AS P 25 BOPD/LANS
3304-3450 8/9/62

DST (1) 3237-79/1 HR, G/10", FLO
1/58", BHP 1005-985/30", FP
280-755#

DST (2) 3284-3310/1 HR, G/9", 3260'
GSY O, BHP 1060-1010#, FP 245-
735#

DST (3) 3315-55/1 HR, 180' G, 180'
GCW, BHP 995-980#
(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS