

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22141-00-00
Spot: CN2NWNE Sec/Twnshp/Rge: 24-19S-14W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: WEST Well Number: 1
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 5399 Conductor Pipe: Size _____ feet:
Op Name: AMERICAN ENERGIES CORPORATION Surface Casing: Size 8.625 feet: 206 165 sx cmt
Address: 155 N. MARKET, STE 710 Production: Size 4.5 feet: 3479 150 sx cmt 113.10
WICHITA, KS 67202 Liner: Size _____ feet:

Well Type: EOR UIC Docket No: E22063.1 Date/Time to Plug: 01/10/2001 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: BUTCH JACKSON Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/10/2001 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:
Set retrievable plug at 2960' and topped with 20' sand.
260' to 561' - squeezed with 250 sxs cement and 3% ccl.
324' to 551' - squeezed with 135 sxs 60/40 pozmix - 2% ccl.
477' - squeezed hole with 200 sxs common - cement broke in above at 292'.
Decided to plug and abandoned.
Tied onto 4 1/2" casing and pumped to pressure with 125 sxs - 200# hulls.
Max. P.S.I. 800#. S.I.P. 300#.
Hooked onto annulus instant pressure 800#.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 2001
1-16-01
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED
DATE 1/17/01
INV. NO. 2001061271

JAN 11 2001

RAYMOND OIL COMPANY INC
 ONE MAIN PLACE #900
 WICHITA, KS 67202

#1 WEST 24-19-14W
 C N/2 NW NE

CONTR DUKE DRILLING CO INC CTY BARTON

GEOL ROBERT F. O'DELL FIELD GREAT BEND TWST

E 1867 XB CD/24/80 CARD 4/9/81 IP P 32 BOPD
ISSUED LANS 3312-3352 OA

API 15-009-22,141

LOG TOPS	DEPTH	DATUM
ANH	778	+1089
TOP	2744	- 877
HEEB	3080	-1213
BR LM	3174	-1307
LANS	3190	-1323
B KC	3387	-1520
ARB NOT REPORTED		
LTD	3464	-1597
RTD	3480	-1613

8-5/8" 2DE/165sx, 4 1/2" 3479/150

DST (1) 3180-3245/30-45-30-45, REC 20' M, SIP 75-75#, FP 53-43/64-53#

DST (2) 3241-3276/30-45-30-45, REC 5' VSQSM, SIP 60-50#, FP 60-40/50-40#

DST (3) 3267-3290/30-45-30-45, 372' GIP, REC 92' O&GCM W/WTR, SIP 559-580#, FP 100-70/90-80#

DST (4) 3303-3365/30-45-30-45, 1713' GIP, REC 105' HGCM, 605' HGC & FROTHY OIL, SIP 740-644#, FP 107-258/301-312#

DST (5) 3471-3480/30-45-30-45, REC 248' GCM, 397' GCSW, SIP 1154-1194#, NO FP, TOOL PLUGGING

MICT - CO, PF 4/3350-52, 12/3332-38, 12/3312-18, AC 1500, SWB LD, POP

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS