

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03465-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 7-16S-13W
1814 feet from S Section Line, 1815 feet from W Section Line
Lease/Unit Name: HOFFMAN A Well Number: 7
County: BARTON Total Vertical Depth: 3354 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 645 250 SX CMT
Production: Size 7 feet: 3340 175 SX CMT \$109.01
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2001 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: VAL DREHER Company: EXPRESS WELL SERVICE INC Phone: (785) 483-8356

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 10% gel - 1000# hulls.
Perfs 2972' - 3295'.
Casing parted in the hole.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/27/2001 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran tubing to 905' - pumped 200 sxs 60/40 pozmix with 600# hulls.
Pulled tubing to 500' - pumped 90 sxs 60/40 pozmix with 200# hulls - cement circulated.
Pulled tubing - tied onto 10 3/4" casing - pumped 120 sxs 60/40 pozmix - cement circulated backside.
Pumped 15 more sxs with Max. P.S.I. 500#. S.I.P. 200#.

INVOICED

DATE 7-03-01

INV. NO. 2002060002

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 2 2001
7-2-01

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY - TICKET #6207.

Plugged through: TBG

District: 04

Signed Pat Staab

(TECHNICIAN)