

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04013-00-00  
Spot: CSWSENE Sec/Twnshp/Rge: 32-17S-12W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HOEFFNER Well Number: 4  
County: BARTON Total Vertical Depth: 3385 feet

Operator License No.: 7030  
Operator Name: EVANS, JOHN ROY  
Address: PO 385  
CLAFLIN, KS 67525

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 770 300 sx cmt  
Production: Size 5.5 feet: 3378 100 sx cmt 110.01  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2000 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: BRIAN FRENZEL Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Prod. Perf at 3006'.  
Shot casing at 2000'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/05/2000 12:30 PM KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Sanded back to 2950' and topped with 5 sxs cement with dump bailer.  
Rigged up and shot off casing at 2000'.  
Pulled up to 1500' and pumped 100 sxs cement with 300# hulls.  
Pulled to 800' and spotted 40 sxs cement with 200# hulls.  
Pulled to 350' and circulated cement with 50 sxs.  
Laid casing down.  
Topped with 10 sxs cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 7 2000  
12-7-00  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 12/8/00

INV. NO. 2001061091

Form CP-2/3

DEC 06 2000

BENNETT & ROBERTS

#1 HOFFNER

32-17-12W

53

SW SE NE

Contr. BENNETT & ROBERTS

BARTON

County

E 1828RB Comm. 6-6-58

Comp. 7-4-58

IP

25 BOPD

2  
3

Tops	Depth	Datum
ANH	712	1116
TOP	2703	-875
HEEB	2987	-1159
TOR	3006	-1178
DOUG SH	3018	-1190
BR LM	3082	-1254
LANS	3100	-1272
CONG	3337	-1509
ARB	3352	-1524
TD	3385	-1557

Casing  
8" 770  
5" 3378

DST 3152-92/1 HR, 2000' G, 60' MDY 0, 128'  
HO & GCM, BHP 550#  
CO TD: BL 56 GO & 26 GWPH: ACID 1000:  
SWB 16 BFPH, 9% OIL: PERF 17/3180-83: 48  
GPH & 20 GW: ACID 5000: 63 GO & 33 GWPH:  
PERF 25/3168-72: ACID 1000: 47 GO & 56  
GWPH

REDWING EAST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS