

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04012-00-00
Spot: CW2SWNE Sec/Twnshp/Rge: 32-17S-12W
3300 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: HOEFFNER Well Number: 3
County: BARTON Total Vertical Depth: 3364 feet

Operator License No.: 7030
Operator Name: EVANS, JOHN ROY
Address: PO 385
CLAFLIN, KS 67525

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 432 300 SX CMT
Production: Size 5.5 feet: 3350 175 SX CMT 109.33
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2000 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN FRENZEL Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Prod. Perfs at 2937' - 3131'.
Shot casing off at 2000'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/04/2000 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back to 2900' and topped with 5 sxs cement with dump bailer.
Rigged up and shot off casing at 2000'.
Pulled up to 1500' and pumped 100 sxs cement with 300# hulls.
Pulled to 800' and spotted 40 sxs cement with 200# hulls.
Pulled to 350' and circulated cement with 50 sxs.
Laid Casing down.
Topped with 10 sxs cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 2000
12-7-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 12/8/00

INV. NO. 2001061091

DEC 06 2000

BENNETT & ROBERTS

#3 HOEFLINER

32-17-12W 53

C W2 SW NE

Contr.

BARTON County

E 1832RB Comm.

Comp.

3-30-56 IP 30 BOPD/ARB

Tops	Depth	Datum
Asb	716	+ 1116
HEEB	2992	-1160
TOR	3011	-1179
BR IM	3088	-1256
LANS	3102	-1270
ARB	3350	-1518
TD	3354	-1522

Casing

8" 432

5" 3350 $\frac{1}{2}$

ACID 1000: EST 40-50:
BOPH

REDWING EAST POOL

+	+	+
+	+	+
+	+	+

Pat 0-320

Asb 716-736

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS