

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-07259-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 15-16S-12W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: KRAMER Well Number: 3  
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 6357  
Op Name: WEBCO OIL CO., INC.  
Address: 1303 BAKER AVE.  
GREAT BEND, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 540 275 sxs cmt  
Production: Size 4.5 feet: 3318 150 sxs cmt  
Liner: Size \_\_\_\_\_ feet:

112.13

Well Type: EOR UIC Docket No: E16938.1 Date/Time to Plug: 11/30/2000 1:00 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: N.R. WEBER 11/30 Company: WEBCO OIL COMPANY Phone: (316) 583-3539

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Tubing stuck in the hole form 877' to TD.  
Injection Zone 3051' - 3450'.  
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/30/2000 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Klima Well service ran tubing to 869'.  
Allied tied onto and circulated cement with 230 sxs and 400# hulls.  
Laid tubing down and topped off hole with 20 sxs.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 02 2001  
1-2-01

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 1/3/00

INV. NO. 2001061234

Form CP-2/3

DEC 28 2000

DERBY OIL COMPANY

#3

KRAMER

NW NW NW 7

Contr.

PEEL DRILLING COMPANY

BARTON

County

E

1869

Comm.

Comp.

1-6-50

IP

56 BOPD &amp; 6 BW

Tops	Depth	Datum
LANS	3055	-1186
ARB	3319	-1450
T.D.	3322	-1453

Casing

8" 540 DST 3056-94, OP 25 MIN,  
 5" 3320 REC 430' OIL CUT MUD  
 900' OIH/9 HRS: ACID  
 200: SWB 2 3/4 BOPH/10  
 HRS: PB 3250' PERF  
 3058-68, 28S, 3051-58  
 ACID 1500: RMP 36 BO/  
 18 HRS: ACID 3000


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS