

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03460-00-00
Spot: CE2SW Sec/Twnshp/Rge: 7-16S-13W
1320 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: HOFFMAN A Well Number: 2
County: BARTON Total Vertical Depth: 3359 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 646 250 SX CMT
Production: Size 7 feet: 3340 175 SX CMT
Liner: Size _____ feet: _____ \$109.17

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2001 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: VAL DREHER Company: EXPRESS WELL SERVICE INC Phone: (785) 483-3144

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 10% gel - 1/4# flocele - 500# hulls.
Perfs 2795' - 3269'. Bridge plug at 3313'.
Casing leaks.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/26/2001 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 955' - pumped 200 sxs cement with 500# hulls.
Pulled to 500' - tied onto tubing and pumped 100 sxs cement with 100# pump pressure.
Pulled to 250' - tied onto tubing and pumped 35 sxs cement.
Pulled tubing and tied onto backside - pumped 35 sxs backside to circulate cement.
Tied onto casing and pumped an additional 30 sxs with Max. P.S.I. 650#. S.I.P. 400#.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 29 2001
6-29-01
CONSERVATION DIVISION

INVOICED
DATE 6-29-01
INV. NO. 2001062027

Remarks: ALLIED CEMENTING COMPANY - TICKET #6204.

Plugged through: TBG

District: 04

Signed Pat Staab
(TECHNICIAN)

JUN 27 2001