

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03466-00-00
Spot: NWSEWWSW Sec/Twnshp/Rge: 7-16S-13W
1813 feet from S Section Line, 828 feet from W Section Line
Lease/Unit Name: HOFFMAN A Well Number: 8
County: BARTON Total Vertical Depth: 3365 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 638 w/250 sxs cmt
Production: Size 7 feet: 3327 w/175 sxs cmt
Liner: Size _____ feet: 109.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2001 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE INC
Proposal Rcvd. from: VAL DREHER Company: EXPRESS WELL SERVICE INC Phone: (785) 483-8356

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 10% gel - 800# hulls.
Perfs 2891' - 3188'. OA. BP's 3210' and 3000'.
Casing was parted in the hole.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/27/2001 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing 860' - pumped 180 sxs 60/40 pozmix with 500# hulls. Cement circulated.
Pulled tubing - tied onto casing - pumped 120 sxs 60/40 pozmix to circulate cement on backside.
Pumped an additional 10 sxs with Max. P.S.I. 500#. S.I.P. 400#.

INVOICED
DATE 7-3-01
INV. NO. 2002060002
RECEIVED
KANSAS CORPORATION COMMISSION
JUL 2 2001
7-2-01
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY - TICKET #6208.

Plugged through: TBG

District: 04

Signed Pat Staab

(TECHNICIAN)

JUN 27 2001