

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21537-01-00  
Spot: SWSWSWSE Sec/Twnshp/Rge: 22-30S-21W  
231 feet from S Section Line, 2434 feet from E Section Line  
Lease Name: B.W.B. OF KANSAS Well #: 1-22 H  
County: CLARK Total Vertical Depth: 5726 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5800		WITH 30 SX CMT
COND	13.375	50		WITH 10 YDS CMT
L1	4.5	8999		405 sx cement
PROD	7	6216	2513	WITH 295 SX CMT
SURF	9.625	808		WITH 530 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2014 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5800' WITH 30 SX CMT. PLUG AT 1200' WITH 30 SX GEL & 50 SX CMT. PLUG AT 830' WITH 75 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 40 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/27/2014 1:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 5800' WITH 30 SX CMT. RTIH TO 1200' & LOADED HOLE WITH MUD. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 830' WITH 75 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
9290	9999		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD. <sup>MTD</sup> ~~FMD~~ = 10.095 <sub>cm</sub>

Plugged through: TBG

KCC WICHITA

JUL 03 2014

RECEIVED

District: 01

RECEIVED

JUL - 1 2014

KCC DODGE CITY

Signed

7.23.14 CKM

(TECHNICIAN)

Invoiced for 4,369'