

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22368-00-00
Spot: NWNE Sec/Twnshp/Rge: 32-6S-20W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MOLLHAGEN Well #: 5
County: ROOKS Total Vertical Depth: 3773 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3372		150 sx
SURF	8.625	259		180 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/11/2014 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL Phone: (785) 483-2025

Proposed Plugging Method: PC at 1968' w/350 sx cement.
LKC Perforations: 3618' - 3654'
CIBP at 3680'
ARB at 3704' - 3708'
Cleaned out casing to 3650' with bit. Started losing hole. Sand and cuttings. Decided to plug and abandon.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2014 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3590'. Tagged rough casing. Pulled tubing to 3560'. Quality pumped 100 sx cement w/200 # hulls. Pulled tubing to 2250' and pumped 100 sx cement w/100 # hulls. PTOH. Topped off 4 1/2" casing with 15 sx cement full. Dug out backside and pumped 10 sx cement. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3704	3708		
3652	3652		
3651	3654		
3634	3634		
3633	3635		
3620	3620		
3618	3621		

Remarks: QUALITY OILWELL CEMENTING TICKET # 512

Plugged through: TBG

KCC WICHITA

JUL 21 2014

RECEIVED

District: 04

Signed Richard Williams
7-23-14 CKM (TECHNICIAN) (M)

JUL 17 2014