

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20070-00-00  
Spot: W2W2NW Sec/Twnshp/Rge: 16-14S-19W  
3960 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: KINDERKNECHT B Well #: 1  
County: ELLIS Total Vertical Depth: 3853 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3850		75 SX
SURF	8.625	213		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2014 11:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1197

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/10/2014 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations at 2000', 1450', 750' and 215'. Ran tubing to 3600' and pumped 11 sx gel followed by 50 sx cement. Pulled tubing to 2000' and pumped 100 sx cement. Pulled tubing to 1000' and pumped 150 sx cement. Cement circulated out back side and braden head. POOH. Hooked to casing and pumped 40 sx cement. Circulated cement out braden head. Shut in braden head and pressured up to 350 psi to shut in.

GPS: 38.83818 -099.44663

Perfs:

Top	Bot	Thru	Comments
3819	3823		
3796	3799		
3782	3786		

Remarks: QUALITY CEMENTING TICKET # 262

Plugged through: TBG

KCC WICHITA  
JUL 22 2014  
RECEIVED

District: 04

Signed Ray A. Dinkel  
7-23-14 CKM (TECHNICIAN) CM

JUL 17 2014