

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20328-00-01
Spot: N2NWNW Sec/Twnshp/Rge: 14-19S-15W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: SCHROEDER Well #: 2
County: BARTON Total Vertical Depth: 3456 feet

Operator License No.: 5617
Op Name: THE PYRAMID CORPORATION, INC.
Address: 1030 VINCENT ST
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3454 | | 200 SX |
| SURF | 8.625 | 899 | | 425 SX |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/07/2014 9:30 AM
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.
Proposal Rcvd. from: JIM LINE Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Emergency plug because well was found to be flowing.
No CP-1 or T-1 as of time of report.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2014 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

07/07/2014- (Witnessed by Bruce Rodie) Ran tubing to 3250' and pumped 70 sx cement. Pulled tubing to 2350' and pumped 60 sx cement. Pulled tubing to 1500' and pumped 40 sx cement. Pulled tubing to 900' and pumped 40 sx cement. Pulled tubing to 400' and pumped 190 sx cement with no returns. Shut down for the night. Rained out.
07/14/2014- (Witnessed by Ray Dinkel) Ran tubing to 252'. Tagged up and pumped 30 sx cement. Cement circulated to surface. POOH. Hooked to casing and pumped 10 sx cement at 200 psi. Braden head was found to be full of cement. 07/15/2014- Cut off casing and it was full of cement.

GPS: 38.40451 -098.95708

Perfs:

Remarks: COPELAND ACID AND CEMENT TICKET # 42772 AND 42717

Plugged through: TBG

KCC WICHITA
JUL 22 2014
RECEIVED

District: 04

Signed

Ray A. Dinkel
7-23-14

(TECHNICIAN)

CM

JUL 17 2014