

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25031-00-00
Spot: N2SWSWNW Sec/Twnshp/Rge: 36-20S-11W
2060 feet from N Section Line, 330 feet from W Section Line
Lease Name: HAMMEKE Well #: 1-36
County: BARTON Total Vertical Depth: 3401 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3398		120 SX
SURF	8.625	330		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2014 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 655-4494

Proposed Plugging Method: Production perforations: 2976' - 2983' and 3302' - 3329'.
Set CIBP at 2900' w/2 sx cement on top
Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 10 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2014 8:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Set CIBP at 2900' w/2 sx cement on top. Cut casing at 1475'. Pulled casing to 1350'. Allied pumped 10 sx gel followed w/125 sx cement w/200 # hulls. Pulled casing to 970' and pumped 50 sx cement w/100 # hulls. Pulled casing to 480'. Allied pumped 100 sx cement w/100 # hulls to circulate cement to surface. Pulled casing out of hole. Topped off 8 5/8" casing w/25 sx cement.

Perfs:

Top	Bot	Thru	Comments
3302	3316		

KCC WICHITA

Remarks: ALLIED TICKET # 063592

JUL 22 2014
RECEIVED

Plugged through: CSG

District: 04

Signed Richard Williams
7.23.14 CKM (TECHNICIAN)

CM