

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22220-00-00
Spot: NENWSW Sec/Twnshp/Rge: 27-14S-16W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: ROHLEDER Well #: 1
County: ELLIS Total Vertical Depth: 3387 feet

Operator License No.: 4787
Op Name: TDI
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3362		150 SX
SURF	8.625	193		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2014 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF CRAWFORD Company: BLACK OPS WELL SERVICE Phone: (785) 871-7311

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls and 7 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/07/2014 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1600' and 195'. Express ran in hole with tubing to 3016'. Global rigged to tubing and pumped 7 sx gel followed by 50 sx cement w/100 # hulls mixed in. Pulled tubing to 1605'. Casing parted near surface. Operator called a welder. Pumped 180 sx cement to circulate cement up 4 1/2" casing. Pulled tubing. Cut off 8 5/8" casing and topped off with 15 sx cement. Hole standing full.

GPS: 38.80473 -099.09258

Perfs:

Top	Bot	Thru	Comments
3286	3287		
3269	3270		
3246	3247		
3133	3134		
3109	3110		

KCC WICHITA

Remarks: (SOS) GLOBAL TICKET # 1375


JUL 21 2014

Plugged through: TBG

RECEIVED

District: 04

Signed


7-23-14 *gem* (TECHNICIAN)

CM

JUL 14 2014