

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24223-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 34-8S-19W
455 feet from S Section Line, 1975 feet from W Section Line
Lease Name: AMREIN Well #: 3
County: ROOKS Total Vertical Depth: 3514 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347		205 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/14/2014 12:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: DERBY Company: AMERICAN EAGLE DRILLING LLC Phone: (785) 303-0377

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 07/14/2014 11:15 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3428 w/50 sx
2nd plug @1470 w/50 sx
3rd plug @825 w/100 sx
4th plug @400 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

KCC WICHITA
JUL 22 2014
RECEIVED

District: 04

Signed Ed Schumacher
7-23-14 ccm (TECHNICIAN)

CM

JUL 17 2014