

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21653-00-00
Spot: SWNENW Sec/Twnshp/Rge: 2-18S-13W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: TINDALL Well #: 4
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3372		151 SX
SURF	8	418		274 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2014 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRE Company: VAMCO OPERATIONS Phone: (620) 727-3409

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 500 # hulls and 12 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2014 9:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1400', 715' and 300'. Ran tubing to 3000' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 130 sx cement w/200 # hulls. Cement circulated out back side. POOH. Hooked to braden head and pumped 40 sx cement. Circulated cement out casing. Shut in casing and pressured up to 300 psi.

GPS: 38.51920 -098.73264

Perfs:

Remarks: QUALITY WELL SERVICE TICKET # 6210

Plugged through: TBG

KCC WICHITA
JUL 22 2014
RECEIVED

District: 04

Signed R. AD Intel
7-23-14 CLEM (TECHNICIAN)

CM

JUL 17 2014