

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05638-00-00
Spot: SESWNW Sec/Twnshp/Rge: 12-11S-18W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: RIDLER A WEST B Well #: #1
County: ELLIS Total Vertical Depth: 3417 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	12	100		125 sx
PROD	4.5	3417		175 sx
SURF	8.625	1117		325 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2014 10:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Packer stuck in hole at 2505'. CIBP at 3115'. Perforations at 3365' - 3377'.
09/13- Squeezed 1369 - 1401', 2604' - 2700' w/250 sx cement
Squeezed 2604' - 2700' w/25 sx cement.
9/26- Squeezed 1022'. Cement circulated up 8 5/8" casing and 12" casing w/250 sx cement.
Emergency plug with rig over hole.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2014 2:05 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Chito's ran in hole with tubing to 2500'. Swift mixed and pumped 100 sx cement. Pulled tubing to 1000' and pumped 80 sx cement to circulate cement up 4 1/2" casing. Pulled tubing. Rigged to 4 1/2" casing and pumped 25 sx cement. Hole standing full.

GPS: 39.11064 -099.27445

Perfs:

Remarks: SWIFT SERVICES TICKET # 26709

Plugged through: TBG

KCC WICHITA
JUL 22 2014
RECEIVED

District: 04

Signed _____

7-23-14 CKM

(TECHNICIAN)

CM

JUL 17 2014