

To: 1 051671
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-15

API NUMBER 15- 033-20,298-0000
C NW SW, SEC. 13, T. 34 S, R. 20 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30972
Operator: Bishop Operating Company Inc.
Name & Address P.O. Box 1807
Hutchinson, KS 67504

Lease Name G.C. Lemon Well # 5
County Comanche
Well Total Depth 4850 ^{157.62} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 781

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 15 Month: 6 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 4847' w/150 sx cement, Perfs at 4782-87'
1st plug sand back to 4730' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, and 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1:15 p.m. Day: 15 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 5 sx cement on top of sand
through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, and 125 sx cement.
Maximum pressure 550 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(Do not observe this plugging.)

INVOICED
DATE 6-24-93
BY, NO. 37989

Signed Richard W. Lacy
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1993
6-18-93
CONSERVATION DIVISION
Wichita, Kansas