

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-08226-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 3-9S-16W  
330 feet from S Section Line, 990 feet from W Section Line  
Lease Name: GAMBLE Well #: 9  
County: ROOKS Total Vertical Depth: 3420 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3419		150 SX
SURF	8.625	227		190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2014 10:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-2540

Proposed Plugging Method: Worked on well for 2 days. Unable to get below 1030'. Losing hole at 300' everytime. Trip out of hole. Out of casing at 1030'.  
Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/30/2014 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 980'. Copeland pumped 180 sx cement to surface out both 5 1/2" production casing and 8 5/8" surface pipe. Backed tubing off at 313'. PTOH. Hooked up to 5 1/2" casing and squeezed 40 sx cement. Maximum pressure 500 psi. Shut in pressure 500 psi.

Perfs:

Top	Bot	Thru	Comments
3121	3330		

KCC WICHITA  
AUG 07 2014  
RECEIVED

Remarks: COPELAND TICKET # 42678

Plugged through: TBG

District: 04

Signed Richard Williams  
8-11-14 CKM (TECHNICIAN) CM

JUL 31 2014