

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22380-00-00
Spot: SESWSSEW Sec/Twnshp/Rge: 12-20S-29W
166 feet from S Section Line, 1939 feet from W Section Line
Lease Name: JASPER 12V Well #: 1 SWD
County: LANE Total Vertical Depth: 5771 feet

Operator License No.: 34681
Op Name: ENCANA OIL & GAS (USA) INC.
Address: 5851 LEGACY CIRCLE
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5130		WITH 60 SX CMT
COND	14	80		WITH 56 SX CMT
PROD	7	5169	2350	WITH 205 SX CMT
SURF	9.625	2123		WITH 760 SX CMT

Well Type: SWD UIC Docket No: D31247.0 Date/Time to Plug: 07/17/2014 7:30 AM
Plug Co. License No.: 34602 Plug Co. Name: KEY ENERGY SERVICES, LLC
Proposal Rcvd. from: FURGAN CHAUDHAY Company: ENCANA OIL & GAS Phone: (337) 207-2694

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 60 SX CMT. PLUG AT 2130' WITH 70 SX CMT. PLUG AT 1250' WITH 80 SX CMT. PLUG AT 350' WITH 60 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2014 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 5130' WITH 60 SX CMT. 1ST PLUG AT 2135' WITH 70 SX CMT. 2ND PLUG AT 1250' WITH 80 SX CMT. 3RD PLUG AT 350' WITH 110 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5169	5771	OH	

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 05 2014

Remarks: USED 60/40 POZMIX 4% GEL BY KEY ENERGY.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

RECEIVED
JUL 23 2014
KCC DODGE CITY

Signed Michael Maier
CC: UIC ✓ (TECHNICIAN)
8.12.14 CKM

Form CP-2/3