

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22381-01-00
Spot: SESWSESW Sec/Twnshp/Rge: 12-20S-29W
204 feet from S Section Line, 1975 feet from W Section Line
Lease Name: JASPER 12H Well #: 2
County: LANE Total Vertical Depth: 5350 feet

Operator License No.: 34681
Op Name: ENCANA OIL & GAS (USA) INC.
Address: 5851 LEGACY CIRCLE
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4730		WITH 60 SX CMT
COND 14		80		WITH 56 SX CMT
L1 4.5		8937	0	WITH 435 SX CMT
PROD 7		5350	2238	WITH 220 SX CMT
SURF 9.625		2118		WITH 760 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/12/2014 8:00 AM
Plug Co. License No.: 34602 Plug Co. Name: KEY ENERGY SERVICES, LLC
Proposal Rcvd. from: FURGAN CHAUDHAY Company: ENCANA OIL & GAS Phone: (469) 304-6345

Proposed Plugging Method: SET CIBP IN MISSISSIPPI WITH 60 SX CMT. PLUG AT 2130' WITH 70 SX CMT. PLUG AT 1250' WITH 80 SX CMT. PLUG AT 350' WITH 60 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/12/2014 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN CIBP TO 4730' WITH 60 SX CMT. 1ST PLUG RUN TBG TO 2135' WITH 70 SX CMT. 2ND PLUG PULLED TBG TO 1250' WITH 80 SX CMT. 3RD PLUG PULLED TBG TO 350' WITH 110 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
8512	8843		
8118	8447		
7727	8055		
7334	7662		
6942	7270		
6550	6878		
6157	6485		
5765	6093		
5372	5700		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 05 2014

CONSERVATION DIVISION
WICHITA, KS

Interval to Bill: 8937-5350=3587'

Remarks: USED 60/40 POZMIX 4% GEL BY KEY ENERGY. TMD = 8937'

Plugged through: CSG

District: 01

RECEIVED

JUL 22 2014

KCC DODGE CITY

Signed

8-12-14 CKM

(TECHNICIAN)

Form CP-2/3